

Die Solaranlage „Futterkamp 2“

Leistung 30 kWp, Inbetriebnahme 2010

Modulfeld	Wechselrichter	Module	Aufbau	Leistung
1	SMA SMC 6000TL Yingli Solar	YL-230 Wp polykristallines Si	2 Strings x 15 Module	6,90 kWp
2a	SMA SPR 3000TL Sunpower	SPR-245-WHT monokristallines Si	1 String x 12 Module	2,94 kWp
2b	SMA SPR 3000TL Sunpower	SPR-245-WHT monokristallines Si	1 String x 12 Module	2,94 kWp
3	SMA SB 5000TL Solar Frontier	SC-85 CIS-Dünnschicht	8 Strings x 7 Module	4,76 kWp
4	SMA SMC 6000TL ITS PolyUp	220 polykristallines Si	2 Strings x 15 Module	6,60 kWp
5	SMA SMC 6000TL Aleo S_16	180 polykristallines Si	2 Strings x 18 Module	6,48 kWp